G. R. S. 59]

GENERAL AND REVENUE SECRETARIAT.

1907.

(Mudgrai.)

File No. 89

Serial Nos. 1—4

Papers Filed.

Month December 1908.

SUBJECT.

Sanctions the repairs to the Sri Agbareswara Swamii and other temples at Ikkeri in the Sagar Taluk

PREVIOUS REFERENCES.	LATER REFERENCES.
M. J. 7 of 1906.	Mudg. J. 412—08.
	" 547—10.

Serial No.

On the requisition made by the Deputy Commr: to have the work carried out by the agency of the P. W Department, the Chief Engineer informed this Office that he did not approve of the proposal to add a Zinc roof Verandah to this ancient temple of architectural beauty, as he feared that it would spoil the Symmetry of the temple. Accordingly, he was requested that a modified Estimate might be prepared and forwarded early, the cost being kept within the amount now Sanctioned.

In forwarding 2 alternative Estimates one amounting to Rs 2009/- for removing the top plaster and a portion of the old Concrete over the Covering slabs of the roof of the temple and for putting 2" thick fine cement Concrete and the other amounting to Rs 2820/- for introducing thin expanded metal armouring in the cement Concrete to secure more substantial envelope over the existing roofing, the Chief Engineer recommends that Sanction to the latter Estimate may be accorded though the cost exceeds the original Sanctioned Estimate by Rs 762/-

The excess amount of Rs 762/- has to be Sanctioned from the State Grant

The Estimate for Rs 2820/- includes the Sum of Rs 191/- being the

NOTE—Contn. sheet.

GPB—50,000—18-5 06

G. R. S. 12]
General and Revenue Secretariat.

File No. 89 of 1907

Serial No.

Establishment & Tools & Plant charges, charged by the D.P.W. Considering that the temple is one of architectural interest and the fact that a sum of Rs 1262 has to be met out of the State Grant, it is a matter for consideration whether the Establishment & charges should not be waived in this case.

Submitted for orders.

4/12/08

Let me first know if this money sanctioned last year has been credited to this Temple or if it has lapsed.

3/12/08

Off mbr 1-12-08 – [illegible]

Sir.

Put up draft sanctioning the exemption.

2-12-1908

Off mbr 2-12-1908 – Draft submitted herewith.

No. 285 4/12/08

Considered.

2.12.1908

Approved

4.12.1908

4/12/08

7

NOTE—Contn. sheet.

GPB—50,000—13-5 08

G. R. S. 12.
General and Revenue
Secretariat

File No. [illegible] of 190[illegible]

Serial
No.

1236

No. 6436 13-9

Mysore Public Works Department,
Central Office,
Dated Bangalore, 9th September 1907.

From,

W. H. Hutchin Esquire, M.I.C.E.,
Chief Engineer of Mysore,
BANGALORE.

To,

L. Anantasami Rao Esquire, B.A.,
Secretary to the Government
of His Highness the Maharaja of Mysore,
Fuzrai Department,
BANGALORE.

Sir,

With reference to Government Proceedings No. 6058-9 dated the 25th June 1907, sanctioning an estimate amounting to Rs. 2,058 for repairing the temple of Sri Aghoreswaraswami, paravatamma and Nandikeswara, at Ikkeri in the Sagar Taluk, I have the honor to inform you that the Superintending Engi--neer, Western Circle, who was requested by the Deputy Commis--sioner to have the work carried out by the agency of this Department does not approve of the proposal to add a zinc roof verandah to this ancient temple of architectural beauty as he fears that it will spoil the symmetry of the temple and be incongruous. I am therefore of opinion that the Superintending Engineer may be asked to work out somethin better and suggest this course being followed.

I have the honor to be,
Sir,
Your most obedient servant,

Captain R.E.
For Chief Engineer of Mysore.

21/9

Mar 1]

To The Chief Engineer
of Calicut

Dated

Despatched

Received

General No

No. Marine 2957-2

Enclosure No.

Sir,

With reference to
your letter no 6436 dt 9th
September 1907 regarding the
repairs to the Sri Agnores-
wara Swami temple at
Dharkoti in the Sagar Taluk
am directed to state
I have the honor to report
that as the temple building
is one of historical
and architectural interest

GPB—3,000—21-7-06

a modified estimate,
as proposed
may be prepared and ~~sent~~ forwarded early,
by your Department the
cost ~~of which~~ being, with
within the amount now
The estimates already sanctioned must on the
~~sanctioned. In respect the Forces~~
sanctioned. ~~of early a portion being given~~ meantime be held
I have &c in abeyance.

Secretary.

Copy is forwarded to the
Hon'ble Shimoga Dt, for
~~information~~, together with
a copy of the Chief Engr's
letter no 6447/56 D, 9th Septr 1907
on the subject, for information.

BO

Secretary.

19/9/07

MYSORE P. W. DEPARTMENT,

No. 7227

CENTRAL OFFICE,

BANGALORE, 18th November 1908.

From

THE CHIEF ENGINEER OF MYSORE,

BANGALORE.

To

K.S.Chandrasekara Iyer Esquire,B.A.,B.L.,

Secretary to the Government of

His Highness the Maharaja of Mysore,

General & Revenue Departments.

SIR,

In compliance with the Muzrai Secretary's letter No. 1647 of the 25th September 1907, I have the honor to for--ward for your disposal, 2 alternative estimates one amounting to Rs. 2,009/- for removing the top plaster and a portion of the old concrete over the covering slabs of the roof of the Sri Aghoreswaraswami Temple at Ikkere in Sagar Taluk and for putting on 2" thick fine cement concrete and the other amount--ing to Rs. 2,820/- for introducing thin expanded metal armouring in the cement concrete to secure more substantial envelope over the existing roofing and to recommend sanction to the latter estimate though the cost exceeds the original sanctioned estimate amount by Rs. 762/-

2. The original sanctioned estimate is also forwarded for information.

3. This disposes of your reminder No. 152 of 4th instant.

I have the honor to be,

Sir,

Your most obedient servant,

For Deputy Chief Engineer

of Mysore.

MYSORE P. W. DEPARTMENT.

No. 7227

From

THE CHIEF ENGINEER OF MYSORE,

Bangalore.

To

Dated Bangalore,

Despatched

4 Plans
3 Statials

Enclosure No. 8. 1 Report

SUBJECT.

G.R.S. 28]

89-07
File No. ~~53~~ 68
Serial No. 2

Diary No. of letter replied to–

Proceedings of the Government of His Highness the Maharaja of Mysore

GENERAL AND REVENUE SECRETARIAT.
( )

, *the* 190

Date of issue 7.12.1908.

Signed by Rao A.S. Iyer.

READ—
Government Pro No. 6058-9 Dt 25th June 1907 Sanctioning an Estimate amounting to Rs 2058/- for repairing the Sri Aghoreswara Swamy Parvatamma and Nandikeswara Swamy temples at Ikkeri in the Sagar Taluk

~~ORDER THEREON.~~ No.
Correspondence ending to the letter No. 7227 dated 18th November 1908 from the Chief Engineer of Bangalore forwarding two alternative Estimates for Rs 2009/- and Rs 2820/- for thorough repairs to the above temples and recommending that Sanction to

SUBJECT

2nd F 89-07-4

the latter Estimate may be accorded.

order thereon No 380-2

2nd F 152-89-07-4

In the Government order of 89 of

7.12.1907

Ex. 1.8

the 25th June 1907 read above an Estimate for Rs 2058/- for repairing the Sri Aghoreswara Swami and other temples at Akkeri was sanctioned and the work was ordered to be executed under the personal Supervision of the Amildar. The temple being of historical and architectural interest, the Deputy Commissioner requested that the work may be executed by the P. W Department

The Chief Engineer forwards two alternative Estimates for Rs 2,009/- and Rs 2820/- for thorough repairs to the temple and recommends that the latter estimate for Rs 2820/- which provides for introducing thin expanded metal armouring in the cement Concrete to Secure envelope on the

G.R.S. 27]

GENERAL AND REVENUE SECRETARIAT.

(Continuation Sheet draft form.)

existing roofing, may be Sanctioned. Under the Circumstances recommended by the Chief Engineer, the revised Estimate for Rs 2820/- (inclusive of charges for establishment and Tools and Plant) is sanctioned, Rs 762/- being met from the State Grant of the Current Official year 1908-9 and the balance from the Savings at the credit of the Institution which include the Sum of Rs 500/- Sanctioned from the State Grant of last year.

3. The work will be executed by the Public works Department. The Comptroller is requested to place the Sanctioned Sum of Rs 2820/- at the disposal of the Chief Engineer.

4. The original Estimate Sanctioned in the Proceedings read above is hereby Cancelled.

G.
J. R. Cart
for Secretary

4/12/08

Fair draft)
4/12

To
The Chief Engr. with the Sanctd Estimate, Plan & other enclosures.
" Comptroller, Mysore Govt.
" Dy Comr Shimoga District

MGCPB—30,000—5-4-05.